

File: F-0.0 Skyline 24x36 CURRENT.dwg Plotted by: BobH Date: 16-May-17 2:20:34pm



LAYOUT LEGEND

-  SYNTHETIC TURF AND PERMEABLE AGGREGATE
-  SYNTHETIC TURF INFIELD AND PERMEABLE AGGREGATE
-  AREA OF RE-GRADED BASE AGGREGATE TRANSITION TO ACCOMMODATE NEW SUPPLEMENTAL PAD SYSTEM
-  EXISTING CHAINLINK FENCE AND CONCRETE CURB
-  EXISTING CHAINLINK FENCE
-  EXISTING CHAINLINK FENCE WITH NEW FABRIC
-  EXISTING LIMIT OF SYNTHETIC TURF AND CONCRETE EDGE ANCHOR
-  CATCH BASIN INLET (C.B.I.) TYPE 1
-  CATCH BASIN INLET (C.B.I.) TYPE 2
-  1" QUICK COUPLER VALVE AND BOX (13)

LAYOUT NOTES

1. THE CONTRACTOR SHALL SECURE ANY UNSECURED PROJECT AREAS WITH 6 FOOT HIGH TEMPORARY CHAINLINK FENCING.
2. FURNISH AND INSTALL NEW BASES AND PLATES IN THE INFIELD AREA AS SHOWN. EXISTING BASE ANCHORS TO REMAIN OR MAY BE REPLACED WITH NEW AT THE CONTRACTOR'S OPTION.
3. FURNISH AND INSTALL SOCCER GOAL ANCHORS AS INDICATED. PROVIDE 2 GROUND ANCHORS WITH TURF COVER FOR EACH SOCCER GOAL. EXACT LOCATION OF ANCHORS SHALL CONFORM WITH ACTUAL BACKSTAY LOCATION OF SOCCER GOALS - ANTICIPATED TO BE 8.5'. **ALTERNATE BID #2:** FURNISH AND INSTALL NEW SOCCER GOALS.
4. SYNTHETIC TURF INFILL TO MATCH FLUSH WITH EXISTING CONCRETE CURBS AT ALL GATE LOCATIONS.
5. **ALTERNATE BID # 1:** REMOVE AND REPLACE 9 GAUGE CHAIN LINK FENCING FABRIC WITH 6 GAUGE FENCING FABRIC. SEE FENCING PLAN F-1.2 FOR EXACT LOCATION.
6. INSTALL NEW IRRIGATION QUICK COUPLER AND VALVE BOX WITH SYNTHETIC TURF COVER. INSTALL 4"x4" INLAID BLUE SQUARE AT THE CENTER OF LID TO MARK LOCATION (13 TOTAL).
7. RE-GRADE DISTURBED AGGREGATE BASE TO MEET PLANARITY AND INFILTRATION RATE REQUIREMENTS. THE CONTRACTOR SHALL HAVE PROJECT ENGINEER AND SYNTHETIC TURF INSTALLATION FOREMAN APPROVED BASE BEFORE BEGINNING THE SYNTHETIC TURF INSTALLATION.
8. FURNISH AND INSTALL SUPPLEMENTAL PAD SYSTEM. PROVIDE GRADE TRANSITION AT PERIMETER OF FIELD FOR INSTALLATION OF SUPPLEMENTAL PAD SYSTEM.
9. PROTECT AND UTILIZE EXISTING EDGE ANCHOR TO SECURE NEW SYNTHETIC TURF SURFACING AROUND THE FIELD PERIMETER. MAKE REPAIRS AS NEEDED.
10. PROTECT ALL EXISTING UTILITIES TO REMAIN THROUGHOUT CONSTRUCTION.
11. CONTRACTOR SHALL FIELD VERIFY SYNTHETIC TURF SURFACING DIMENSIONS TO MATCH EXISTING FIELD. SEE SYNTHETIC TURF COMPOSITE LAYOUT PLAN FOR SYNTHETIC TURF LINES AND MARKINGS.


NOTE LEGEND

1. (INDICATES GENERAL CONSTRUCTION NOTE)
3. (INDICATES SPECIFIC CONSTRUCTION KEYNOTE)

REVISION	DATE



SKYLINE COMMUNITY FIELD SYNTHETIC TURF REPLACEMENT



ISSUE FOR BID	
DATE	01-31-17
SCALE	1"=30'
DRAWN	JNM/DMD
CHECKED	RSH
COPYRIGHT © 2017 D.A. HOGAN & ASSOCIATES	

COLOR LAYOUT PLAN