



Inglewood Hill Stormwater and Non-motorized Improvement Project

**Public Meeting
January 7, 2015
6 – 8pm**

The Inglewood Hill Stormwater and Non-motorized Improvement Project proposes to construct stormwater conveyance pipe, stormwater quality treatment facilities, and non-motorized improvements in the Inglewood Hill area. The project will include approximately:

- 5,700 linear feet of tightline stormwater conveyance pipe
- 30 foot x 60 foot sand filter vault for stormwater quality treatment
- 7 modular wetland systems for stormwater quality treatment
- Replacement of existing stormwater outfall to Lake Sammamish
- 3,200 linear feet of empty conduit for future fiber optics
- 3,200 linear feet of curbing, sidewalk, planter strips, and bike lanes on Inglewood Hill Road NE from ELSP to 212th Ave NE
- Asphalt restoration and overlay of project limits

The project is in the final stages of design. Residents should expect the following project schedule:

Jan – Feb 2016	Final Design, Permitting, Public Outreach, Easement Negotiations
Mar 2016	Advertise and Bid Construction Contract
Apr – Oct 2016	Construction
July – Aug 2017	Asphalt Restoration and Overlay
Oct 2017	Project Closeout

Construction impacts may include:

- Limited, partial road closures and traffic delay (10 min maximum queue)
- Temporary reduced shoulder parking and driveway access
- Vegetation removal and landscape restoration coordination
- Typical construction dust and noise

The City has received the following grants for the project:

\$850,000	King County Flood Control District Sub-regional Opportunity Grant
\$250,000	King County Flood Reduction Grant

Construction costs are estimated to be \$4.6 M.